Form 3160-3
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0136
Expires November 30, 2000

001

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No.: U-33433

6. If Indian, Allottee or Tribe Name:

1a. Type of Work: [X] DRILL [ ] REENTER

7. If Unit or CA Agreement, Name and No.:

b. Type of Well: [ ] Oil Well [X] Gas Well [ ] Other [ ] Single Zone [ ] Multiple Zone

8. Lease Name and Well No.: BONANZA 1023-5O

2. Name of Operator: WESTPORT OIL & GAS COMPANY, L.P.

9. API Well No.: 43-047-35438

3A. Address: 1368 SOUTH 1200 EAST, VERNAL, UT 84078

3b. Phone No. *(include area code)*: (435)781-7060

10. Field and Pool, or Exploratory: BONANZA

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*

At surface: SWSE 4425908Y 39.97343 -109.34642 641211X

At proposed prod. Zone: 903' FSL 1609' FEL 39.97318 N LAT, 109.34710 W LON

11. Sec., T., R., M., or Blk, and Survey or Area: SEC 5-T10S-R23E MER UBM

14. Distance in miles and direction from nearest town or post office*: 27.4 MILES 400' SOUTHEAST OF OURAY, UTAH

12. County or Parish: Uintah

13. State: Utah

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any): 903'

16. No. of Acres in lease: 1922.95

17. Spacing Unit dedicated to this well: 320

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft: refer to Topo "C"

19. Proposed Depth: 8600' MD

20. BLM/BIA Bond No. on file: BLM BOND # CO-1203

21. Elevations (Show whether DF, KDB, RT, GL, etc.): 5261' GL

22. Approximate date work will start*: Upon Approval

23. Estimated duration: To Be Determined

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office.
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized office.

25. Signature: Debra Domenici — Name *(Printed/Typed)*: Debra Domenici — Date: 12/30/2003

Title: SR ADMINISTRATIVE ASSISTANT

Approved by *(Signature)*: — Name *(Printed/Typed)*: BRADLEY G. HILL — Date: 01-29-04

Title: — Office: ENVIRONMENTAL SCIENTIST III

Federal Approval of this Action is Necessary

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**(Instructions on reverse)*

RECEIVED
JAN 12 2004
DIV. OF OIL, GAS & MINING

T10S, R23E, S.L.B.&M.



WESTPORT OIL AND GAS COMPANY, L.P.

Well location, BONANZA #1023-50, located as shown in the SW 1/4 SE 1/4 of Section 5, T10S, R23E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK 58 EAM (1965) LOCATED IN THE NE 1/4 OF SECTION 30, T9S, R23E, S.L.B.&M. TAKEN FROM THE RED WASH SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5132 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

No. 161319
REGISTERED LAND SURVEYOR
REGISTRATION No. 161319
STATE OF UTAH

REVISED: 11-20-03 D.COX

LEGEND:

- ∟ = 90° SYMBOL
- ● = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(AUTONOMOUS NAD 83)
LATITUDE = 39°58'23.45" (39.973181)
LONGITUDE = 109°20'49.55" (109.347097)

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE: 1" = 1000'	DATE SURVEYED: 10-03-03	DATE DRAWN: 10-08-03
PARTY: D.K. J.S. D.COX	REFERENCES: G.L.O. PLAT	
WEATHER: WARM	FILE: WESTPORT OIL AND GAS COMPANY, L.P.	

BONANZA #1023-5O
SW/SE Sec. 5, T10S,R23E
UINTAH COUNTY, UTAH
U-33433

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. **Estimated Tops of Important Geologic Markers:**

Formation	Depth
Uinta	0- Surface
Green River	1247'
Wasatch	4140'
Mesaverde	6230'
TD	8600'

2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

Substance	Formation	Depth
	Green River	1247'
Gas	Wasatch	4140'
Gas	Mesaverde	6230'
Water	N/A	
Other Minerals	N/A	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program.

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program.

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program.

6. **Evaluation Program:**

Please refer to the attached Drilling Program.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 8600' TD, approximately equals 3440 psi (calculated at 0.4 psi/foot).

Maximum anticipated surface pressure equals approximately 1548 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Drilling Program.

10. **Other Information:**

Please refer to the attached Drilling Program.

Westport Oil and Gas Company, L.P.

DRILLING PROGRAM

COMPANY NAME	Westport Oil and Gas Co., L.P.		DATE	January 7, 2004	
WELL NAME	**BONANZA 1023-5O**		TD	8,600' MD/TVD	
FIELD	Natural Buttes	COUNTY Uintah	STATE Utah	ELEVATION	5,254' GL KB 5,269'
SURFACE LOCATION	903' FSL, 1609' FEL, SWSE SEC.5, T10S, R23E			BHL	Straight Hole
	Lat (39.972081) Long (109.346319)				
OBJECTIVE ZONE(S)	Wasatch/Mesaverde				
ADDITIONAL INFO	Regulatory Agencies: BLM (MINERALS & SURF), UDOGM, Tri-County Health Dept.				

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		20'		14"	
			12-1/4"	9-5/8", 32.3#, H-40, STC	Air mist
Catch water sample, if possible, from 0 to 4,140'					
	Green River @ 1,247 Preset f/ GL @ 2000 MD				
Mud logging program TBD Open hole logging program f/ TD - surf csg			7-7/8"	4-1/2",11.6#,M80,I80 or equivalent LTC csg	Air Mist/Polymer Aerated Water/Brine 8.3-10.0 ppg
	Wasatch @ 4,140'				
	Mverde @ 6,230'				
	TD @ 8,600'				Max anticipated Mud required 10.0 ppg

Westport Oil and Gas Company, L.P.

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS BURST	COLLAPSE	TENSION
CONDUCTOR	16"	0-20'						
						2270	1370	254000
SURFACE	9-5/8"	0 to 2000	32.30	H-40	STC	0.88********	1.46	4.49
						7780	6350	201000
PRODUCTION	4-1/2"	0 to 8600	11.60	M-80	LTC	3.02	1.42	2.31

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point)

2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 10.0 ppg) .22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MASP 2580 psi

******** Burst SF is low but csg is much stronger than formation at 2000'. EMW @ 2000' for 2270# is 21.8 ppg or 1.13 psi/ft

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
Option 1	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	50		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE			**NOTE: If well will circulate water to surface, option 2 will be utilized**				
Option 2	LEAD	1500	65/35 Poz + 6% Gel + 10 pps gilsonite +.25 pps Flocele + 3% salt BWOW	360	35%	12.60	1.81
	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,640'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	400	60%	11.00	3.38
	TAIL	4,960'	50/50 Poz/G + 10% salt + 2% gel +.1% R-3	1390	60%	14.30	1.31

*Substitute caliper hole volume plus 15% excess if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

DRILLING ENGINEER: _____ **DATE:** _____

Brad Laney

BONANZA #1023-5O
SW/SE SEC. 5, T10S, R23E
UINTAH COUNTY, UTAH
U-33433

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. **Existing Roads:**

Directions to the proposed location are attached.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. **Planned Access Roads:**

The proposed access road is approximately 400' +/-. Refer to Topo Map B.

The access road will be crowned (2 to 3%), ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet. Graveling or capping the roadbed will be performed as necessary to provide a well constructed, safe road. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. 1989.

The road surface and shoulders will be kept in a safe and usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free-flowing and will be maintained according to original construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing or shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches, and the turnouts kept clear so that snowmelt will be channeled away from the road.

3. **Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing & Proposed Facilities:**

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The requested color is Carlsbad Canyon (2.5 Y 6/2) as determined during the on-site inspection.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Refer to Topo Map D for the placement of the proposed pipeline.

5. **Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec.32, T4S,R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. **Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. **Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner is to be used as discussed during on-site inspection. It will be a minimum of 16 mil thick and felt, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec.35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E. (Request is in lieu of filing Form 3160-5, after initial production).

8. **Ancillary Facilities:**

None are anticipated.

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **Plans for Reclamation of the Surface:**

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. **Surface Ownership:**

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
(435) 789-1362

12. **Wildlife Stipulations:**

Golden Eagle Stipulations:

No construction February 1 through July 15.

13. **Other Information:**

A Class III archaeological survey and a paleontological survey have been completed and the reports will be submitted separately.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance. The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

Seed Mixture:

Scarlet Globemallow	4 lb/acre
Shadscale	4 lb/acre
Crested Wheatgrass	1 lb/acre
Galleta Grass	3 lb/acre

13. **Lessee's or Operators's Representative & Certification:**

Debra Domenici
Sr. Administrative Assistant
Westport O&G Co.
P.O. Box 1148
Vernal, UT 84078
(435) 781-7060

Randy Bayne
Drilling Manager
Westport O&G Co.
P.O. Box 1148
Vernal, UT 84078
(435)781-7018

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Westport Oil &Gas Company is considered to be the operator of the subject well. Westport Oil & Gas Company agrees to be responsible under the terms and the conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for the lease activities is being provided by BLM Nationwide Bond #CO-1203.

I hereby certify that the proposed drill site and access route has been inspected and that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

Debra Domenici

December 22, 2003
Date

WESTPORT OIL AND GAS COMPANY, L.P.
BONANZA #1023-5O
SECTION 5, T10S, R23E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 5.1 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 1.6 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTHEAST; FOLLOW ROAD FLAGS IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 400' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 58.5 MILES.

WESTPORT OIL AND GAS COMPANY

BONANZA #1023-5O

LOCATED IN UINTAH COUNTY, UTAH
SECTION 5, T10S, R23E, S.L.B.&M.



PHOTO: VIEW FROM LOCATION STAKE TO CORNER #3 CAMERA ANGLE: EASTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS CAMERA ANGLE: SOUTHEASTERLY

- Since 1964 -
Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS	10 MONTH	21 DAY	03 YEAR	PHOTO
TAKEN BY: D.K.	DRAWN BY: P.M.	REVISED: 11-21-03		



LEGEND:

⊙ PROPOSED LOCATION

N

WESTPORT OIL AND GAS COMPANY, L.P.

BONANZA #1023-5O
SECTION 5, T10S, R23E, S.L.B.&M.
903' FSL 1609' FEL

Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP	10 MONTH	21 DAY	03 YEAR	A TOPO
SCALE: 1:100,000	DRAWN BY: P.M.	REVISED: 11-21-03		



LEGEND:

EXISTING ROAD

PROPOSED ACCESS ROAD

N

WESTPORT OIL AND GAS COMPANY, L.P.

BONANZA #1023-5O
SECTION 5, T10S, R23E, S.L.B.&M.
903' FSL 1609' FEL

Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP	10 MONTH	21 DAY	03 YEAR	B TOPO
SCALE: 1" = 2000'	DRAWN BY: P.M.	REVISED: 11-21-03		



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

N

WESTPORT OIL AND GAS COMPANY, L.P.

BONANZA #1023-5O
SECTION 5, T10S, R23E, S.L.B.&M.
903' FSL 1609' FEL

Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP	10 MONTH	21 DAY	03 YEAR
SCALE: 1" = 2000'	DRAWN BY: P.M.	REVISED: 11-21-03	C TOPO



APPROXIMATE TOTAL PIPELINE DISTANCE = 500' +/-

LEGEND:

PROPOSED ACCESS ROAD
EXISTING PIPELINE
PROPOSED PIPELINE

N

WESTPORT OIL AND GAS COMPANY, L.P.

BONANZA #1023-5O
SECTION 5, T10S, R23E, S.L.B.&M.
903' FSL 1609' FEL

Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP	10 MONTH	21 DAY	03 YEAR	D TOPO
SCALE: 1" = 1000'	DRAWN BY: P.M.	REVISED: 11-21-03		

WESTPORT OIL AND GAS COMPANY, L.P.

LOCATION LAYOUT FOR

BONANZA #1023-50

SECTION 5, T10S, R23E, S.L.B.&M.

903' FSL 1609' FEL



SCALE: 1" = 50'
DATE: 11-20-03
Drawn By: D.COX

Proposed Access Road

18" CMP Required

CONSTRUCT DIVERSION DITCH

Sta. 3+50

C-7.5'
El. 67.6'

C-6.6'
El. 66.7'

C-2.6'
El. 62.9'

Approx. Top of Cut Slope

NOTE:
Flare Pit is to be located a min. of 100' from the Well Head.

Topsoil Stockpile

Existing Drainage

PIPE TUBS

PIPE RACKS

CATWALK

El. 80.9'
C-30.8'
(btm. pit)

FLARE PIT

C-4.9'
El. 65.0'

Blooie Line

C-3.6'
El. 63.7'

C-0.8'
El. 60.9'

F-3.6'
El. 56.5'

Sta. 1+50

RIG

135'

22'

38'

100'

MUD TANKS

DOG HOUSE

TOILET

TRAILER

RESERVE PITS
(10' Deep)

LIGHT PLANT

BOILER

COMPRESSOR

BOOSTER

PUMP HOUSE

WATER TANK

MUD TANKS

15' WIDE BENCH

150'

Total Pit Capacity
W/2' of Freeboard
= 14,440 Bbls. ±
Total Pit Volume
= 3,920 Cu. Yds.

Sta. 0+15

1 1/2:1 Slope

TRASH

150'

F-3.2'
El. 56.9'

PROPANE STORAGE

35'

Approx. Toe of Fill Slope

Round Corners as Needed

El. 59.2'
C-9.1'
(btm. pit)

Sta. 0+00

F-7.8'
El. 52.3'

Reserve Pit Backfill & Spoils Stockpile

F-1.0'
El. 59.1'

NOTES:

Elev. Ungraded Ground At Loc. Stake = 5260.9'

FINISHED GRADE ELEV. AT LOC. STAKE = 5260.1'

FIGURE #1

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

WESTPORT OIL AND GAS COMPANY, L.P.

FIGURE #2

TYPICAL CROSS SECTIONS FOR

BONANZA #1023-50
SECTION 5, T10S, R23E, S.L.B.&M.
903' FSL 1609' FEL

1" = 20'
X-Section Scale
1" = 50'

DATE: 11-20-03
Drawn By: D.COX

REGISTERED LAND SURVEYOR No. 161319 ROBERT L. KAY STATE OF UTAH



NOTE:
Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE YARDAGES

CUT
(6") Topsoil Stripping = 1,590 Cu. Yds.
Remaining Location = 12,710 Cu. Yds.

TOTAL CUT = 14,300 CU.YDS.
FILL = 3,840 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION = 10,260 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.) = 3,550 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation) = 6,710 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

3,000 PSI

BOP STACK





005

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 01/05/2004

API NO. ASSIGNED: 43-047-35438

WELL NAME: BONANZA 1023-5O
OPERATOR: WESTPORT OIL & GAS CO (N2115)
CONTACT: DEBRA DOMENICI

PHONE NUMBER: 435-781-7060

PROPOSED LOCATION:
SWSE 05 100S 230E
SURFACE: 0903 FSL 1609 FEL
BOTTOM: 0903 FSL 1609 FEL
UINTAH
NATURAL BUTTES (630)

LEASE TYPE: 1 - Federal
LEASE NUMBER: U-33433
SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: MVRD

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LATITUDE: 39.97343

LONGITUDE: 109.34642

RECEIVED AND/OR REVIEWED:

✓ Plat
✓ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. CO-1203)
N Potash (Y/N)
N Oil Shale 190-5 (B) or 190-3 or 190-13
✓ Water Permit
(No. 43-8496)
N RDCC Review (Y/N)
(Date:)
N/A Fee Surf Agreement (Y/N)

LOCATION AND SITING:

___ R649-2-3.

Unit _____

___ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells

___ R649-3-3. Exception

✓ Drilling Unit
Board Cause No: 179-9 (4/320')
Eff Date: 12-28-99
Siting: 460' fr drl u boundry & 920' fr other wells

___ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: 1- Federal approval



OPERATOR: WESTPORT O&G CO (N2115)

SEC. 5 T.10S, R.23E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH

CAUSE: 179-9 / 12-28-1999 (4/320')

Utah Oil Gas and Mining

Wells
- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL

Unit Status
- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Field Status
- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

N
W E
S

PREPARED BY: DIANA WHITNEY
DATE: 7-JANUARY-2004

002

WESTPORT OIL AND GAS COMPANY, L.P.

1670 Broadway Suite 2800 Denver Colorado 80202
Telephone: 303 573 5404 Fax: 303 573 5609

January 26, 2004

Ms. Diana Whitney
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, UT 84114-6100
FAX 801-359-3940

RE: Exception Location
Bonanza 1023-5 O
8,600' Mesaverde well
903' FSL, 1,609' FEL (SW/4SE/4) Sec 5-T10S-R23E
Uintah County, Utah
Bonanza Prospect

Dear Ms. Whitney:

Westport Oil and Gas Company, L.P. plans to drill the captioned well to a depth of 8,600' to test the Wasatch and Mesaverde formations. The well is located at an exception location to Spacing Order 179-9 because the well is located closer than 920' from Westport's Southman Canyon 4-5 well (1,620' FSL, 1,020' FEL). The Bonanza 1023-5 O well location was selected to stay away from an eagle's nest to the south

Attached is a copy of a letter indicating approval of the exception location from EOG Resources, Inc., owners of leasehold in Sec 32 and 33, the north offset to the spacing unit for our well. Westport owns the remaining leasehold being infringed upon by the exception location.

Westport requests your approval of this exception location to Spacing order 179-9. If you have any questions, call me at 303-607-3445. Thank you for your assistance.

Sincerely,

Bruce E. Johnston
Land Manager
BEJ/209a
cc Debra Domenici

003

WESTPORT OIL AND GAS COMPANY, L.P.

1670 Broadway Suite 2800 Denver Colorado 80202
Telephone: 303 573 5404 Fax: 303 573 5609

January 21, 2004

Ms. Debbie Spears
EOG Resources, Inc.
600 17th Street
Ste. 1100N
Denver, CO 80206

RE: Exception Location
Bonanza 1023-5 O
8,600' Mesaverde Well
T10S-R23E, Sec 5: SW/4SE/4 (903' FSL, 1,609' FEL)
Uintah County, Utah
Bonanza Prospect UT115

Dear Ms. Spears:

Westport Oil and Gas Company have requested a permit to drill the captioned well. The Bonanza 1023-5 O well is in a legal location spot in accordance with Spacing Order 179-9, but it is approximately 800' from Westport's SC 4-5 well (1,620' FSL, 1,020 FEL). The well had to be moved to this exception location due to an eagle nest south of the location, which we must be avoided. EOG Resources owns an interest in All of Sec 32 and 33-T9S-R23E offsetting our 320-acre spacing unit for the captioned well.

We request your acceptance of this exception location. Please sign and return a copy of this letter indicating acceptance.

Thank you for your assistance and immediate response.

Sincerely,

Bruce E. Johnston
Land Manager
BEJ/208
cc: Sheila Upchego

Accepted and agreed to this 23 day of January 2004.

EOG Resources, Inc.

J. Michael Schween
Agent and Attorney-in-Fact

006

State of Utah

Department of
Natural Resources

Division of
Oil, Gas & Mining

ROBERT L. MORGAN
Executive Director

LOWELL P. BRAXTON
Division Director

MICHAEL O. LEAVITT
Governor

OLENE S. WALKER
Lieutenant Governor

January 29, 2004

Westport Oil & Gas Company L.P.
1368 South 1200 East
Vernal, UT 84078

Re: Bonanza 1023-5O Well, 903' FSL, 1609' FEL, SW SE, Sec. 5, T. 10 South, R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann.§ 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-35438.

Sincerely,

John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Westport Oil & Gas Company L.P.

Well Name & Number Bonanza 1023-5O

API Number: 43-047-35438

Lease: U-33433

Location: SW SE **Sec.** 5 **T.** 10 South **R.** 23 East

Conditions of Approval

1. General

   Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

   Notify the Division within 24 hours of spudding the well.

   - Contact Carol Daniels at (801) 538-5284.

   Notify the Division prior to commencing operations to plug and abandon the well.

   - Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

   All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

Form 3160-5
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

008

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

5. Lease Serial No.
U-33433

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

8. Well Name and No.
BONANZA 1023-5O

2. Name of Operator
WESTPORT OIL & GAS COMPANY L.P
Contact: SHEILA UPCHEGO
E-Mail: supchego@westportresourcescorp.com

9. API Well No.
43-047-35438

3a. Address
1368 SOUTH 1200 EAST
VERNAL, UT 84078

3b. Phone No. (include area code)
Ph: 435.781.7024
Fx: 435.781.7094

10. Field and Pool, or Exploratory
BONANZA

4. Location of Well *(Footage, Sec., T., R., M., or Survey Description)*
Sec 5 T10S R23E SWSE 903FSL 1609FEL

11. County or Parish, and State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
☐ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off
☒ Subsequent Report	☐ Alter Casing	☐ Fracture Treat	☐ Reclamation	☐ Well Integrity
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☒ Other Well Spud
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon	
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

MIRU PETE MARTIN DRILLING. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 60# STEEL CONDUCTOR PIPE. CMT W/28 SX READY MIX CMT.

SPUD WELL LOCATION ON 9/2/04 AT 0700 HRS.

RECEIVED
SEP 2 1 2004
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.
Electronic Submission #36050 verified by the BLM Well Information System
For WESTPORT OIL & GAS COMPANY L.P, sent to the Vernal

Name *(Printed/Typed)* SHEILA UPCHEGO — Title REGULATORY ANALYST

Signature (Electronic Submission) — Date 09/14/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____ Title _____ Date _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

007

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR WESTPORT O&G COMPANY L.P
ADDRESS 1368 SOUTH 1200 EAST
VERNAL, UTAH 84078

OPERATOR ACCT. NO. N 2115

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION QQ	SC	TP	RG	COUNTY	SPUD DATE	EFFECTIVE DATE
A	99999	14296	43-047-35510	BONANZA 1023-7P	SESE	7	10S	23E	UINTAH	9/3/2004	9/15/04 K

WELL 1 COMMENTS:
MIRU PETE MARTIN BUCKET RIG MVRD
SPUD WELL LOCATION ON 9/3/04 AT 6:00 AM

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION QQ	SC	TP	RG	COUNTY	SPUD DATE	EFFECTIVE DATE
A	99999	14297	43-047-35438	BONANZA 1023-5O	SWSE	5	10S	23E	UINTAH	9/2/2004	9/15/04 K

WELL 2 COMMENTS:
MIRU PETE MARTIN BUCKET RIG MVRD
SPUD WELL LOCATION ON 9/2/04 AT 6 AM.

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION QQ	SC	TP	RG	COUNTY	SPUD DATE	EFFECTIVE DATE
B	99999	2900	43-047-35796	NBU 921-31C	NENW	31	9S	21E	UINTAH	9/11/2004	9/14/04 K

WELL 3 COMMENTS:
MIRU PETE MARTIN BUCKET RIG MVRD
SPUD WELL LOCATION ON 9/11/04 AT 1700 HRS
CONFIDENTIAL

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION QQ	SC	TP	RG	COUNTY	SPUD DATE	EFFECTIVE DATE

WELL 4 COMMENTS:

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION QQ	SC	TP	RG	COUNTY	SPUD DATE	EFFECTIVE DATE

WELL 5 COMMENTS:

ACTION CODES (See instructions on back of form)
A - Establish new entity for new well (single well only)
B - Add new well to existing entity (group or unit well)
C - Re-assign well from one existing entity to another ex
D - Re-assign well from one existing entity to a new enti
E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.
(3/89)

Post-it® Fax Note 7671 | Date | # of pages ▶
To ERLENE RUSSELL | From SHEILA UPCHEGO
Co./Dept. UT DOGM | Co. WESTPORT OIL & GAS CO
Phone # (801) 538-5330 | Phone # (435) 781-7024
Fax # (801) 359-3940 | Fax # (435) 781-7094

Signature Sheila Upchego
REGULATORY ANALYST 09/14/04
Title Date
Phone No. (435) 781-7024

RECEIVED
SEP 14 2004
DIV. OF OIL, GAS & MINING

SEP-14-2004 TUE 09:07 AM EL PASO PRODUCTION FAX NO. 4357817094 P. 01

Form 3160-5
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

009

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

5. Lease Serial No.
U-33433

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

8. Well Name and No.
BONANZA 1023-5O

2. Name of Operator
WESTPORT OIL & GAS COMPANY, LP
Contact: SHEILA UPCHEGO
E-Mail: SUPCHEGO@KMG.COM

9. API Well No.
43-047-35438

3a. Address
1368 SOUTH 1200 EAST
VERNAL, UT 84078

3b. Phone No. (include area code)
Ph: 435-781-7024

10. Field and Pool, or Exploratory
BONANZA

4. Location of Well *(Footage, Sec., T., R., M., or Survey Description)*
Sec 5 T10S R23E SWSE 903FSL 1609FEL

11. County or Parish, and State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
☐ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off
☒ Subsequent Report	☐ Alter Casing	☐ Fracture Treat	☐ Reclamation	☐ Well Integrity
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☒ Other Drilling Operations
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon	
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

MIRU BILL MARTIN AIR RIG. DRILLED 12 1/4" SURFACE HOLE TO 1940'. RAN 9 5/8" 32.3# H-40 CSG. CMT W/200 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DROP PLUG DISP W/145 BBLS. LAND PLUG MIX & PM 100 SX CLASS G @15.8 PPG 1.15 YIELD. PMP 100 SX CLASS G @15.8 PPG 1.15 YIELD. PMP 325 SX CLASS G @15.8 PPG 1.15 YIELD. PMP 150 SX CLASS G @15.8 PPG 1.15 YIELD. HOLE STAYED FULL

WORT

RECEIVED
OCT 25 2004
DIV OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.
Electronic Submission #50053 verified by the BLM Well Information System
For WESTPORT OIL & GAS COMPANY, LP, sent to the Vernal

Name *(Printed/Typed)* SHEILA UPCHEGO — Title OPERATIONS

Signature (Electronic Submission) — Date 10/14/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By — Title — Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. — Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

Form 3160-5
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE – Other instructions on reverse side

5. Lease Serial No.
U-33433

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

8. Well Name and No.
BONANZA 1023-5O

2. Name of Operator
WESTPORT OIL & GAS COMPANY L.P.

9. API Well No.
43-047-35438

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. *(include area code)*
(435) 781-7024

10. Field and Pool, or Exploratory Area
BONANZA

4. Location of Well *(Footage, Sec., T., R., M., or Survey Description)*
SWSE SECTION 5-T10S-R23E 903'FSL & 1609'FEL

11. County or Parish, State
UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
☐ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off
☒ **Subsequent Report**	☐ Alter Casing	☐ Fracture Treat	☐ Reclamation	☐ Well Integrity
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☒ **Other FINAL DRILLING OPERATIONS**
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon	
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

FINISHED DRILLING FROM 1940' TO 8253'. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG.
LEAD CMT W/315 SX PREM LITE II @11.3 PPG 3.01 YIELD.
TAILED CMT W/1250 SX 50/50 POZ @14.3 PPG 1.31 YIELD.
FLOATS HELD NO CMT TO SURFACE

RELEASED CAZA 82 ON 5/2/05 AT 1800 HRS,

RECEIVED
MAY 10 2005
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name *(Printed/Typed)*	Title
Sheila Upchego	Regulatory Analyst
Signature	Date
	May 4, 2005

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Form 3160-5
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE – Other instructions on reverse side

5. Lease Serial No.
U-33433-

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

8. Well Name and No.
BONANZA 1023-5O

2. Name of Operator
WESTPORT OIL & GAS COMPANY L.P.

9. API Well No.
43-047-35438

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. *(include area code)*
(435) 781-7024

10. Field and Pool, or Exploratory Area
BONANZA

4. Location of Well *(Footage, Sec., T., R., M., or Survey Description)*
SWSE SECTION 5-T10S-R23E 903'FSL & 1609'FEL

11. County or Parish, State
UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
☐ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off
☒ Subsequent Report	☐ Alter Casing	☐ Fracture Treat	☐ Reclamation	☐ Well Integrity
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☒ Other PRODUCTION START-UP
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon	
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 5/22/05 AT 9:30 AM.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

14. I hereby certify that the foregoing is true and correct

Name *(Printed/Typed)*
Sheila Upchego

Title
Regulatory Analyst

Signature
Sheila Upchego

Date
May 23, 2005

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

RECEIVED
JUN 0 1 2005
DIV. OF OIL, GAS & MINING

WESTPORT OIL & GAS COMPANY, LP
CHRONOLOGICAL HISTORY

BONANZA 1023-5O

	SPUD Air Rig	Surface Casing	Activity	Status
7/19/04			Build Location, 5% complete	Caza 82
7/20/04			Build Location, 45% complete	Caza 82
7/21/04			Build Location, 45% complete	Caza 82
7/22/04			Build Location, 65% complete	Caza 82
7/23/04			Build Location, 65% complete	Caza 82
7/26/04			Build Location, 65% complete	Caza 82
7/27/04			Build Location, 65% complete	Caza 82
7/28/04			Build Location, 65% complete	Caza 82
7/29/04			Build Location, 65% complete	Caza 82
7/30/04			Build Location, 65% complete	Caza 82
8/2/04			Build Location, 65% complete	Caza 82
8/3/04			Build Location, 65% complete	Caza 82
8/4/04			Build Location, 65% complete	Caza 82
8/5/04			Build Location, 65% complete	Caza 82
8/6/04			Build Location, 65% complete	Caza 82
8/9/04			Build Location, 65% complete	Caza 82
8/10/04			Build Location, 65% complete	Caza 82
8/11/04			Build Location, 65% complete	Caza 82
8/12/04			Build Location, 65% complete	Caza 82
8/13/04			Build Location, 65% complete	Caza 82
8/16/04			Build Location, 65% complete	Caza 82
8/17/04			Build Location, 75% complete	Caza 82

8/18/04	Build Location, 85% complete	Caza 82
8/19/04	Build Location, 85% complete	Caza 82
8/20/04	Build Location, 85% complete	Caza 82
8/23/04	Build Location, 85% complete	Caza 82
8/24/04	Build Location, 95% complete	Caza 82
8/25/04	Build Location, 95% complete	Caza 82
8/26/04	Location Built, WOBR	Caza 82
8/27/04	Location Built, WOBR	Caza 82
8/30/04	Location Built, WOBR	Caza 82
8/31/04	Location Built, WOBR	Caza 82
9/1/04	Location Built, WOBR	Caza 82
9/2/04	Location Built, WOBR	Caza 82
9/3/04	Location Built, WOBR	Caza 82
9/7/04	Location Built, WOBR	Caza 82
9/8/04	Location Built, WOBR	Caza 82
9/9/04	Location Built, WOBR	Caza 82
9/10/04	Location Built, WOBR	Caza 82
9/13/04	Location Built, WOBR	Caza 82
9/14/04	Location Built, WOBR	Caza 82
9/15/04	Location Built, WOBR	Caza 82
9/16/04	Location Built, WOBR	Caza 82
9/17/04	Location Built, WOBR	Caza 82
9/20/04	Location Built, WOBR	Caza 82
9/21/04	Location Built, WOBR	Caza 82
9/22/04	Location Built, WOBR	Caza 82
9/23/04	Location Built, WOBR	Caza 82
9/24/04	Location Built, WOBR	Caza 82

9/27/04		14" @ 40'	WOAR	Caza 82
9/28/04		14" @ 40'	WOAR	Caza 82
9/29/04		14" @ 40'	WOAR	Caza 82
9/30/04		14" @ 40'	WOAR	Caza 82
10/1/04		14" @ 40'	WOAR	Caza 82
10/4/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/5/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/6/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/7/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/8/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/11/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/12/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/13/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/14/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/15/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/18/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/19/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/20/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/21/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/22/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/25/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/26/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/27/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/28/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
10/29/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
11/1/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82
11/2/04	10/1/04	9 5/8" @ 1898'		WORT Caza 82

11/3/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/4/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/5/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/8/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/9/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/10/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/11/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/12/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/15/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/16/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/17/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/18/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/19/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/22/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/23/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/24/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/25/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/26/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/29/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
11/30/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/1/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/2/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/3/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/6/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/7/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/8/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/9/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/10/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82

12/13/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/14/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/15/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/16/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/17/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/20/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/21/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/22/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/23/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/27/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/28/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/29/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/30/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
12/31/04	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/03/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/04/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/05/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/06/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/07/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/10/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/11/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/12/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/13/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/14/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/17/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/18/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/19/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82

01/20/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/21/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/24/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/25/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/26/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/27/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/28/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
01/31/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/01/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/02/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/03/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/04/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/07/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/08/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/09/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/10/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/11/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/14/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/15/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/16/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/17/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/18/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/21/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/22/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/23/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/24/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/25/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
02/28/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82

03/01/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/02/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/03/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/04/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/07/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/08/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/09/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/10/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/11/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/14/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/15/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/16/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/17/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/18/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/21/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/22/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/23/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/24/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/25/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/28/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/29/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/30/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
03/31/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/01/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/04/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/05/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/06/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82

04/0705	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/08/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/11/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/12/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/13/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/14/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/15/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/18/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/19/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/20/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/21/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/22/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82
04/25/05	10/1/04	9 5/8" @ 1898'	WORT Caza 82

TD: 2830' Csg. 9 5/8" @ 1892' MW: 8.4 SD: 4/24/05 DSS: 1
Move rig from Bonanza 1023-4G to 1023-5O. Rig up rotary tools. NU and test BOPE. Pick up 7 7/8" PDC bit and Mud Motor. Drill cement and FE. Rotary spud @ 1600 hrs 4/24/05. Drill from 1940'-2830'. DA @ report time.

04/26/05 10/1/04 9 5/8" @ 1898' WORT Caza 82
TD: 4770' Csg. 9 5/8" @ 1892' MW: 8.4 SD: 4/24/05 DSS: 2
Drill from 2830'-4770'. DA @ report time.

04/27/05 10/1/04 9 5/8" @ 1898' WORT Caza 82
TD: 5811' Csg. 9 5/8" @ 1892' MW: 9.1 SD: 4/24/05 DSS: 3
Drill from 4770'-5811'. DA @ report time.

04/28/05 10/1/04 9 5/8" @ 1898' WORT Caza 82
TD: 6625' Csg. 9 5/8" @ 1892' MW: 9.9 SD: 4/24/05 DSS: 4
Drill from 5811'-6428'. Work on #1 pump. Drill to 6625'. DA @ report time.

04/29/05 10/1/04 9 5/8" @ 1898' WORT Caza 82
TD: 7350' Csg. 9 5/8" @ 1892' MW: 10.1 SD: 4/24/05 DSS: 5
Drill from 6625'-7350'. DA @ report time.

05/02/05 10/1/04 9 5/8" @ 1898' WORT Caza 82
TD: 8253' Csg. 9 5/8" @ 1892' MW: 11.8 SD: 4/24/05 DSS: 8
Drill from 7350'-8253' TD. Short trip and CCH. POOH laying down drill string. Run triple combo. Run 4 ½" Production Casing @ report time.

05/03/05 TD: 8253' Csg. 9 5/8" @ 1892' MW: 11.8 SD: 4/24/05 DSS: 9
Finish running 4 ½" production casing and cemented. Set slips, NDBOPE, cut casing, clean mud tanks, and released rig @ 1800 hrs. Moving rig to Bonanza 1023-18DX @ report time.

05/13/05 PROG: 7:00 AM (DAY 1) HELD SAFETY MEETING. DRIVING ON MUDDY ROADS. ROAD RIG FROM BONANZA#1023-18G TO BONANZA#1023-5O SPOT EQUIPMENT. ATTEMPT TO MIRU. SNAPPED AXLE IN REAR END ON RIG. PREP LOCATION. REPAIR RIG. MIRU. SDFN

05/16/05 PROG: 7:00 AM (DAY 2) HELD SAFETY MEETING. PMPS & PRESS. SICP: 150#. CSG SHOE LEAK? BLEW WL DN. NDWH, NUBOP. RU FLOOR & TBG EQUIPMENT. PU 3-7/8" BIT & 122 JTS NEW 2-3/8" J-55 TBG & RIH. (SLM) TBG WAS DRIFTED. EOT @ 3950'. POOH. STANDING BACK TBG. LD BIT. NDBOP, NU (2) 4-1/16" X 10K FRAC VALVES. MIRU CUTTERS. RIH W/4-1/2" CIBP & SET @ 8133'. POOH LD TOOLS. RUN A CBL-CCL-GR LOG FROM 8132' TO 424'. ESTIMATE CMT TOP @ SURFACE'. MAX TEMP 184*. POOH LD TOOLS. MIRU DOUBLE JACK TESTERS. PT 4-1/2" CSG & FRAC VALVES TO 500# & 7500#. (HELD GOOD) RDMO DOUBLE JACK TESTERS. 6:30 PM SWI-SDF-WE PREP TO FRAC W/BJ ON MONDAY 5/16/05.

05/17/05 PROG: FRAC STAGES 1, 2, 3 AS DESIGNED. PREP TO FRAC STAGES 4 & 5 IN AM.

05/18/05 PROG: 7:00 AM (DAY 4) HELD SAFETY MEETING W/CREWS.

STAGE #4: CONTINUE ON. SICP: 330#. BRK DN PERFS @ 4481 @ 4 BPM. PMPD 13 BBLS @ 3380 @ 11 BPM. ISIP: 2040, FG: .74. PMPD 242 BBLS LGHTG 18 GEL & 20,935# 20/40 SD W/207# FLEX SD @ TAIL. ISIP: 4000, FG: 1.0, NPI: 1960, MP: 5226, MR: 11, AP: 3592, AR: 10.8 BPM.

STAGE #5: RIH W/4-1/2" BAKER 5K CBP & PERF GUNS. SET CBP @ 5800'. PERF THE WASATCH @ 5309'-5311' & 5736'-5741' USING 3-1/8" HSC GUNS, 12 GM, 0.34, 90* PHASING, 4 SPF, (28 HLS) BRK DN PERFS @ 2370 @ 4 BPM. PMPD 25 BBLS @ 2780 @ 20 BPM. ISIP: 1400, FG: .68. PMPD 532 BBLS LGHTG 18 GEL & 78,251# 20/40 SD W/1158# FLEX SD @ TAIL. RAMP TO 6 PPG. ISIP: 1950, FG: .79, NPI: 550, MP: 2652, MR: 22.2, AP: 2396, AR: 21.2 BPM. RIH W/4-1/2" BAKER 5K CBP & SET @ 5075'. POOH LD TOOLS. RDMO BJ & CUTTERS. GRAND TOTAL 20/40 & FLEX SD: 997,904#, TOTAL FLEX SD: 14,388# & TOTAL FLUID: 7646 BBLS. ND FRAC VALVES, NUBOP. RU FLOOR & TBG EQUIPMENT. PU 3-7/8" BIT, POBS & RIH ON 62 STANDS OUT OF DERRICK. PU, TALLY & DRIFT 35 JTS. TAG CBP#1 @ 5075'. RU SWVL & PMP. 3:00 PM SWI-SDFN PREP TO DRL OUT (5) CBP'S IN AM.

05/19/05 PROG: 7:00 AM (DAY 5) HELD SAFETY MEETING. DRLG CBP'S. EOT @ 5075'. ESTABLISH CIRC W/2% KCL W/RIG PMP.

(DRLG CBP#1) @ 5075'. DRL OUT BAKER 5K CBP IN 9 MIN. 0# DIFF. RIH, TAG SD @ 5730'. CO 70' SD.

(DRLG CBP#2) @ 5800'. DRL OUT BAKER 5K CBP IN 6 MIN. 0# DIFF. RIH, TAG SD @ 6515'. CO 35' SD.

(DRLG CBP#3) @ 6550'. DRL OUT BAKER 5K CBP IN 9 MIN. 150# DIFF. RIH, TAG SD @ 7395'. CO 35' SD.

(DRLG CBP#4) @ 7430'. DRL OUT BAKER 5K CBP IN 18 MIN. 800# DIFF. RIH, TAG SD @ 7769'. CO 30' SD.

(DRLG CBP#5) @ 7799'. DRL OUT BAKER 10K CBP IN 18 MIN. 150# DIFF. RIH, TAG SD @ 8053'. CO 80' SD TO PBTD @ 8133'. CIRC WL CLEAN, RD SWVL. POOH & LD 21 JTS

ON FLOAT. LAND TBG ON HANGER W/231 JTS NEW 2-3/8" J-55 TBG. EOT @ 7475.90'. POBS W/R NIPPLE @ 7474.48'. AVG 12 MIN/PLUG & C/O 250' SD RD FLOOR & TBG EQUIPMENT. NDBOP, NUWH. DROP BALL & PMP OFF THE BIT @ 1900#. OPEN WL TO PIT ON 20/64 CHK. FTP: 1600#, SICP: 1650#. 4:00 PM TURN WL OVER TO FLOWBACK CREW. ORIG LTR: 7646 BBLS. LTR @ 4:00 PM, 6626 BBLS. RACK EQUIPMENT. RD RIG. ROAD RIG TO BONANZA#1023-18DX. SPOT RIG. 6:00 PM SDFN.

WELL ON FLOWBACK, FLOWBACK REPORT: CP: 1800#, TP: 1775#, 20/64 CHK, 38 BWPH, 16 HRS, SD: TRACE, TTL BBLS FLWD: 1674, TODAYS LTR: 7646 BBLS, LOAD REC TODAY: 1674 BBLS, REMAINING LTR: 5972 BBLS, TOTAL LOAD REC TO DATE: 1674 BBLS.

05/20/05 PROG: WELL ON FLOWBACK, FLOWBACK REPORT: CP: 2150#, TP: 1850#, 20/64 CHK, 25 BWPH, 24 HRS, SD: TRACE, TTL BBLS FLWD: 783, TODAYS LTR: 5972 BBLS, LOAD REC TODAY: 783 BBLS, REMAINING LTR: 5,189 BBLS, TOTAL LOAD REC TO DATE: 2,457 BBLS.

05/23/05 PROG: 5/21/05: WELL ON FLOWBACK, FLOWBACK REPORT: CP: 2300#, TP: 1675#, 20/64 CHK, 12 BWPH, 24 HRS, SD: TRACE, TTL BBLS FLWD: 437, TODAYS LTR: 5189 BBLS, LOAD REC TODAY: 437 BBLS, REMAINING LTR: 4,752 BBLS, TOTAL LOAD REC TO DATE: 2,894 BBLS.

05/22/05: WELL ON FLOWBACK, FLOWBACK REPORT: CP: 2300#, TP: 1550#, 20/64 CHK, 10 BWPH, 24 HRS, SD: CLEAN, TTL BBLS FLWD: 246, TODAYS REC TODAY: 246 BBLS, REMAINING LTR: 4,506 BBLS, TOTAL LOAD REC TO DATE: 3,140 BBLS.

WELL WENT ON SALES. 5/21/05, 9:45 AM. 1800 MCF, 18/64 CHK, SICP: 2300#, FTP: 1630#, 15 BWPH. FINAL REPORT FOR COMPLETION.

Form 3160-4
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: November 30, 2000

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.: U-33433

1a. Type of Well: ☐ Oil Well ☒ Gas ☐ Dry Other
b. Type of Completion: ☒ New ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.
Other

6. If Indian, Allottee or Tribe Name:

7. Unit or CA Agreement Name and No.:

2. Name of Operator: WESTPORT OIL & GAS COMPANY L.P.

8. Lease Name and Well No.: BONANZA 1023-5O

3. Address: 1368 SOUTH 1200 EAST VERNAL, UTAH 84078

3a. Phone No. *(include area code)*: (435) 781-7024

9. API Well No.: 43-047-35438

4. Location of Well *(Report locations clearly and in accordance with Federal requirements)**

At surface: SWSE 903'FSL & 1609'FEL

At top prod. interval reported below

At total depth

10. Field and Pool, or Exploratory: BONANZA

11. Sec., T., R., M., or Block and Survey or Area: SEC 5-T10S-R23E

12. County or Parish: UINTAH

13. State: UTAH

14. Date Spudded: 09/02/04

15. Date T.D. Reached: 05/02/05

16. Date Completed ☐ D & A ☒ Ready to Prod.: 05/22/05

17. Elevations (DF, RKB, RT, GL)*: 5261'GL

18. Total Depth: MD 8253' TVD

19. Plug Back T.D.: MD 8182' TVD

20. Depth Bridge Plug Set: MD TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)

CBL-CCL-GR

22. Was well cored? ☒ No ☐ Yes (Submit copy)
Was DST run? ☒ No ☐ Yes (Submit copy)
Directional Survey? ☒ No ☐ Yes (Submit copy)

23. Casing and Liner Record *(Report all strings set in well)*

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
20"	14"	60#		40'		28			
12 1/4"	9 5/8"	32.3#		1940'		875			
7 7/8"	4 1/2"	11.6#		8253'		1565			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Set (MD)
2 3/8"	7476'							

25. Producing Intervals

	Formation	Top	Bottom
A)	WASATCH	5309'	5741'
B)	MESAVERDE	6494'	8044'
C)			
D)			

26. Perforation Record

Perforated Interval	Size	No. Holes	Perf. Status
5309'-5741'	0.34	28	OPEN
6494'-8044'	0.35	128	OPEN

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and type of Material
5309'-5741'	PMP 532 BBLS LIGHTNING 18 & 78,251# 20/40 FLEX SD
6494'-8044'	PMP 7114 BBLS LIGHTNING 18 & 919,653# 20/40 FLEX SD

RECEIVED
JUN 13 2005
DIV. OF OIL, GAS & MINING

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
05/22/05	05/26/05	24	→	0	2,350	210			FLOWS FROM WELL
Choke Size	**Tbg. Press. Flwg. SI**	**Csg. Press.**	**24 Hr. Rate**	**Oil BBL**	**Gas MCF**	**Water BBL**	**Oil Gravity Corr. API**	**Well Status**	
18/64	1722#	1675#	→	0	2350	210		PRODUCING GAS WELL	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
05/22/05	05/26/05	24	→	0	2350	210			FLOWS FROM WELL
Choke Size	**Tbg. Press. Flwg. SI**	**Csg. Press.**	**24 Hr. Rate**	**Oil BBL**	**Gas MCF**	**Water BBL**	**Oil Gravity Corr. API**	**Well Status**	
18/64	1722#	1675#	→	0	2350	210		PRODUCING GAS WELL	

(See instructions and spaces for additional data on reverse side)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method

Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas : Oil Ratio	Well Status

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method

Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas : Oil Ratio	Well Status

29. Disposition of Gas *(Sold, used for fuel, vented, etc.)*

SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
WASATCH MESAVERDE	4140' 6251'	6251'			

32. Additional remarks (include plugging procedure):

33. Circle enclosed attachments:

1. Electrical/Mechanical Logs (1 full set req'd.)
2. Geologic Report
3. DST Report
4. Directional Survey
5. Sundry Notice for plugging and cement verification
5. Core Analysis
7. Other:

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name *(please print)* SHEILA UPCHEGO Title REGULATORY ANALYST

Signature Sheila Upchego Date 6/7/2005

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

☼ U.S. GPO: 1999-573-624

Division of Oil, Gas and Mining

OPERATOR CHANGE WORKSHEET

ROUTING
1. DJJ
2. CDW

X Change of Operator (Well Sold) Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective: **1/6/2006**

FROM: (Old Operator):	**TO:** (New Operator):
N2115-Westport Oil & Gas Co., LP	N2995-Kerr-McGee Oil & Gas Onshore, LP
1368 South 1200 East	1368 South 1200 East
Vernal, UT 84078	Vernal, UT 84078
Phone: 1-(435) 781-7024	Phone: 1-(435) 781-7024

CA No. **Unit:**

WELL NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
3. The new company was checked on the **Department of Commerce, Division of Corporations Database on:** 3/7/2006
4a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
4b. If **NO**, the operator was contacted contacted on:
5a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
5b. Inspections of LA PA state/fee well sites complete on: n/a
5c. Reports current for Production/Disposition & Sundries on: ok
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject,** for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on:

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database on:** 5/15/2006
2. Changes have been entered on the **Monthly Operator Change Spread Sheet on:** 5/15/2006
3. Bond information entered in RBDMS on: 5/15/2006
4. Fee/State wells attached to bond in RBDMS on: 5/16/2006
5. Injection Projects to new operator in RBDMS on:
6. Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: CO1203
2. Indian well(s) covered by Bond Number: RLB0005239
3. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236

a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
The Division sent response by letter on:

LEASE INTEREST OWNER NOTIFICATION:

4. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

Form 3160-5
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE – Other instructions on reverse side

5. Lease Serial No.
MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

8. Well Name and No.
MUTIPLE WELLS

2. Name of Operator
KERR-McGEE OIL & GAS ONSHORE LP

9. API Well No.

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. *(include area code)*
(435) 781-7024

10. Field and Pool, or Exploratory Area

4. Location of Well *(Footage, Sec., T., R., M., or Survey Description)*
SEE ATTACHED

11. County or Parish, State
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
☐ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off
☒ Subsequent Report	☐ Alter Casing	☐ Fracture Treat	☐ Reclamation	☐ Well Integrity
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☒ Other CHANGE OF OPERATOR
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon	
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006.
KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED
MAY 10 2006
DIV. OF OIL, GAS & MINING

BLM BOND = CO1203
BIA BOND = RLB0005239

APPROVED 5/16/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name *(Printed/Typed)*	Title
RANDY BAYNE	DRILLING MANAGER
Signature	Date
	May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Form 3160-5
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires Jnovember 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE – Other instructions on reverse side

5. Lease Serial No.
MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

8. Well Name and No.
MUTIPLE WELLS

2. Name of Operator
WESTPORT OIL & GAS COMPANY L.P.

9. API Well No.

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. *(include area code)*
(435) 781-7024

10. Field and Pool, or Exploratory Area

4. Location of Well *(Footage, Sec., T., R., M., or Survey Description)*
SEE ATTACHED

11. County or Parish, State
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
☐ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off
☒ Subsequent Report	☐ Alter Casing	☐ Fracture Treat	☐ Reclamation	☐ Well Integrity
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☒ Other CHANGE OF OPERATOR
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon	
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
MAY 10 2006
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name *(Printed/Typed)*	Title
BRAD LANEY	ENGINEERING SPECIALIST
Signature	Date
	May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Brad Laney		5-9-06
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Colorado State Office
2850 Youngfield Street
Lakewood, Colorado 80215-7076

IN REPLY REFER TO:
CO922 (MM)
3106
COC017387 et. al.

March 23, 2006

NOTICE

Kerr-McGee Oil & Gas Onshore L.P. :
1999 Broadway, Suite 3700 : Oil & Gas
Denver, CO 80202 :

Merger/Name Change - Recognized

On February 28, 2006 this office received acceptable evidence of the following mergers and name conversion:

> Kerr-McGee Oil & Gas Onshore L.P., a Delaware Limited Partnership, and Kerr-McGee Oil & Gas Onshore LLC, a Delaware Limited Partnership merger with and into Westport Oil and Gas Company L.P., a Delaware Limited Partnership, and subsequent Westport Oil & Gas Company L.P. name conversion to Kerr-McGee Oil & Gas Onshore L.P.

For our purposes the merger and name conversion was effective January 4, 2006, the date the Secretary of State of Delaware authenticated the mergers and name conversion.

Kerr-McGee Oil & Gas Onshore L.P. provided a list of oil and gas leases held by the merging parties with the request that the Bureau of Land Management change all their lease records from the named entities to the new entity, Kerr-McGee Oil & Gas Onshore L.P. In response to this request each state is asked to retrieve their own list of leases in the names of these entities from the Bureau of Land Management's (BLM) automated LR2000 data base.

The oil and gas lease files identified on the list provided by Kerr-McGee Oil & Gas Onshore L.P. have been updated as to the merger and name conversion. We have not abstracted the lease files to determine if the entities affected by the acceptance of these documents holds an interest in the lease, nor have we attempt to identify leases where the entity is the operator on the ground that maintains vested record title or operating rights interests. If additional documentation, for change of operator, is required you will be contacted directly by the appropriate Field Office. The Mineral Management Services (MMS) and other applicable BLM offices were notified of the merger with a copy of this notice

Please contact this office if you identify additional leases where the merging party maintains an interest, under our jurisdiction, and we will document the case files with a copy of this notice. If the leases are under the jurisdiction of another State Office that information will be forwarded to them for their action.

Three riders accompanied the merger/name conversion documents which will add Kerr-McGee Oil and Gas Onshore LLC as a principal to the 3 Kerr-McGee bonds maintained by the Wyoming State Office. These riders will be forward to them for their acceptance.

The Nationwide Oil & Gas Continental Casualty Company Bond #158626364 (BLM Bond #CO1203), maintained by the Colorado State Office, will remain in full force and effect until an assumption rider is accepted by the Wyoming State Office that conditions their Nationwide Safeco bond to accept all outstanding liability on the oil and gas leases attached to the Colorado bond.

If you have questions about this action you may call me at 303.239.3768.

/s/Martha L. Maxwell
Martha L. Maxwell
Land Law Examiner
Fluid Minerals Adjudication

Attachment:
List of OG Leases to each of the following offices:
MMS MRM, MS 357B-1
WY, UT, NM/OK/TX, MT/ND, WY State Offices
CO Field Offices
Wyoming State Office
Rider #1 to Bond WY2357
Rider #2 to Bond WY1865
Rider #3 to Bond WY1127

United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
http://www.blm.gov

IN REPLY REFER TO:
3106
(UT-922)

March 27, 2006

Memorandum

To: Vernal Field Office

From: Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the merger recognized by the Bureau of Land Management, Colorado State Office. We have updated our records to reflect the merger from Westport Oil and Gas Company L.P. into Kerr-McGee Onshore Oil and Gas Company. The merger was approved effective January 4, 2006.

Chief, Branch of
Fluid Minerals

Enclosure
Approval letter from BLM COSO (2 pp)

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare
Dave Mascarenas
Susan Bauman

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR McGEE OIL & GAS ONSHORE LP
Operator Account Number: N 2995
Address: P.O. Box 173779
city DENVER
state CO zip 80217
Phone Number: (720) 929-6029

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
See Atchmt	See Atchmt						
Action Code	**Current Entity Number**	**New Entity Number**	**Spud Date**			**Entity Assignment Effective Date**	
	99999	18519				5/1/2012	

Comments: Please see attachment with list of Wells in the Ponderosa Unit. 5/30/2012
lwsmvd

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	**Current Entity Number**	**New Entity Number**	**Spud Date**			**Entity Assignment Effective Date**	

Comments:

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	**Current Entity Number**	**New Entity Number**	**Spud Date**			**Entity Assignment Effective Date**	

Comments:

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED
MAY 21 2012
Div. of Oil, Gas & Mining

Cara Mahler
Name (Please Print)

Signature

REGULATORY ANALYST
Title

5/21/2012
Date

(5/2000)

well_name	sec	twp	rng	api	entity		lease	well	stat	qtr_qtr	bhl	surf	zone	a_stat	l_num	op_no
SOUTHMAN CANYON 31-3	31	090S	230E	4304734726	13717		1	GW	P	SENW		1	WSMVD	P	U-33433	N2995
SOUTHMAN CANYON 31-4	31	090S	230E	4304734727	13742		1	GW	S	SESW		1	WSMVD	S	UTU-33433	N2995
SOUTHMAN CYN 31-2X (RIG SKID)	31	090S	230E	4304734898	13755		1	GW	P	NWNW		1	WSMVD	P	U-33433	N2995
SOUTHMAN CYN 923-31J	31	090S	230E	4304735149	13994		1	GW	P	NWSE		1	MVRD	P	U-33433	N2995
SOUTHMAN CYN 923-31B	31	090S	230E	4304735150	13953		1	GW	P	NWNE		1	MVRD	P	U-33433	N2995
SOUTHMAN CYN 923-31P	31	090S	230E	4304735288	14037		1	GW	P	SESE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31H	31	090S	230E	4304735336	14157		1	GW	P	SENE		1	WSMVD	P	U-33433	N2995
SOUTHMAN CYN 923-31O	31	090S	230E	4304737205	16827		1	GW	P	SWSE		1	MVRD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31K	31	090S	230E	4304737206	16503		1	GW	P	NESW		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31G	31	090S	230E	4304737208	16313		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31E	31	090S	230E	4304737209	16521		1	GW	P	SWNW		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31A	31	090S	230E	4304737210	16472		1	GW	P	NENE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31C	31	090S	230E	4304737227	16522		1	GW	P	NENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-1G	01	100S	230E	4304735512	14458		1	GW	P	SWNE		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1A	01	100S	230E	4304735717	14526		1	GW	P	NENE		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1E	01	100S	230E	4304735745	14524		1	GW	P	SWNW		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1C	01	100S	230E	4304735754	14684		1	GW	P	NENW		1	MVRD	P	U-40736	N2995
BONANZA 1023-1K	01	100S	230E	4304735755	15403		1	GW	P	NESW		1	MVRD	P	U-38423	N2995
BONANZA 1023-1F	01	100S	230E	4304737379	16872		1	GW	P	SENW		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1B	01	100S	230E	4304737380	16733		1	GW	P	NWNE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1D	01	100S	230E	4304737381	16873		1	GW	P	NWNW		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1H	01	100S	230E	4304737430	16901		1	GW	P	SENE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1L	01	100S	230E	4304738300	16735		1	GW	P	NWSW		1	MVRD	P	UTU-38423	N2995
BONANZA 1023-1J	01	100S	230E	4304738302	16871		1	GW	P	NWSE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1I	01	100S	230E	4304738810	16750		1	GW	P	NESE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-2E	02	100S	230E	4304735345	14085		3	GW	P	SWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2C	02	100S	230E	4304735346	14084		3	GW	P	NENW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2A	02	100S	230E	4304735347	14068		3	GW	P	NENE		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2G	02	100S	230E	4304735661	14291		3	GW	P	SWNE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2O	02	100S	230E	4304735662	14289		3	GW	P	SWSE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2I	02	100S	230E	4304735663	14290		3	GW	S	NESE		3	WSMVD	S	ML-47062	N2995
BONANZA 1023-2MX	02	100S	230E	4304736092	14730		3	GW	P	SWSW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2H	02	100S	230E	4304737093	16004		3	GW	P	SENE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2D	02	100S	230E	4304737094	15460		3	GW	P	NWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2B	02	100S	230E	4304737095	15783		3	GW	P	NWNE		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2P	02	100S	230E	4304737223	15970		3	GW	P	SESE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2N	02	100S	230E	4304737224	15887		3	GW	P	SESW		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2L	02	100S	230E	4304737225	15833		3	GW	P	NWSW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2F	02	100S	230E	4304737226	15386		3	GW	P	SENW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2D-4	02	100S	230E	4304738761	16033		3	GW	P	NWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2O-1	02	100S	230E	4304738762	16013		3	GW	P	SWSE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2H3CS	02	100S	230E	4304750344	17426		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G3BS	02	100S	230E	4304750345	17428		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G2CS	02	100S	230E	4304750346	17429		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G1BS	02	100S	230E	4304750347	17427		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995

BONANZA 1023-2M1S	02	100S	230E	4304750379	17443		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2L2S	02	100S	230E	4304750380	17444		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2K4S	02	100S	230E	4304750381	17446		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2K1S	02	100S	230E	4304750382	17445		3	GW	P	SENW	D	3	WSMVD	P	ML 47062	N2995
BONANZA 4-6 *	04	100S	230E	4304734751	13841		1	GW	P	NESW		1	MNCS	P	UTU-33433	N2995
BONANZA 1023-4A	04	100S	230E	4304735360	14261		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4E	04	100S	230E	4304735392	14155		1	GW	P	SWNW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4C	04	100S	230E	4304735437	14252		1	GW	P	NENW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4M	04	100S	230E	4304735629	14930		1	GW	P	SWSW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4O	04	100S	230E	4304735688	15111		1	GW	P	SWSE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4I	04	100S	230E	4304735689	14446		1	GW	P	NESE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4G	04	100S	230E	4304735746	14445		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4D	04	100S	230E	4304737315	16352		1	GW	P	NWNW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4H	04	100S	230E	4304737317	16318		1	GW	P	SENE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4B	04	100S	230E	4304737328	16351		1	GW	P	NWNE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4L	04	100S	230E	4304738211	16393		1	GW	P	NWSW		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4P	04	100S	230E	4304738212	16442		1	GW	P	SESE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4N	04	100S	230E	4304738303	16395		1	GW	P	SESW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4FX (RIGSKID)	04	100S	230E	4304739918	16356		1	GW	P	SENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5O	05	100S	230E	4304735438	14297		1	GW	P	SWSE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-5AX (RIGSKID)	05	100S	230E	4304735809	14243		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-5C	05	100S	230E	4304736176	14729		1	GW	P	NENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5G	05	100S	230E	4304736177	14700		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5M	05	100S	230E	4304736178	14699		1	GW	P	SWSW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5K	05	100S	230E	4304736741	15922		1	GW	P	NESW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5B	05	100S	230E	4304737318	16904		1	GW	P	NWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5E	05	100S	230E	4304737319	16824		1	GW	P	SWNW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5H	05	100S	230E	4304737320	16793		1	GW	P	SENE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5N	05	100S	230E	4304737321	16732		1	GW	P	SESW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5L	05	100S	230E	4304737322	16825		1	GW	P	NWSW		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-5J	05	100S	230E	4304737428	17055		1	GW	P	NWSE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5P	05	100S	230E	4304738213	16795		1	GW	P	SESE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-5N-1	05	100S	230E	4304738911	17060		1	GW	P	SESW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5PS	05	100S	230E	4304750169	17323		1	GW	P	NESE	D	1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5G2AS	05	100S	230E	4304750486	17459		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G2CS	05	100S	230E	4304750487	17462		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G3BS	05	100S	230E	4304750488	17461		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G3CS	05	100S	230E	4304750489	17460		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5N4AS	05	100S	230E	4304752080	18484		1	GW	DRL	SWSW	D	1	WSMVD	DRL	UTU73450	N2995
BONANZA 1023-8C2DS	05	100S	230E	4304752081	18507		1	GW	DRL	SWSW	D	1	WSMVD	DRL	UTU37355	N2995
BONANZA 6-2	06	100S	230E	4304734843	13796		1	GW	TA	NESW		1	WSMVD	TA	UTU-38419	N2995
BONANZA 1023-6C	06	100S	230E	4304735153	13951		1	GW	P	NENW		1	MVRD	P	U-38419	N2995
BONANZA 1023-6E	06	100S	230E	4304735358	14170		1	GW	P	SWNW		1	MVRD	P	U-38419	N2995
BONANZA 1023-6M	06	100S	230E	4304735359	14233		1	GW	P	SWSW		1	WSMVD	P	U-38419	N2995
BONANZA 1023-6G	06	100S	230E	4304735439	14221		1	GW	P	SWNE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6O	06	100S	230E	4304735630	14425		1	GW	TA	SWSE		1	WSMVD	TA	U-38419	N2995

* not moved in unit

BONANZA 1023-6A	06	100S	230E	4304736067	14775		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-6N	06	100S	230E	4304737211	15672		1	GW	P	SESW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6L	06	100S	230E	4304737212	15673		1	GW	P	NWSW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6J	06	100S	230E	4304737213	15620		1	GW	P	NWSE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6F	06	100S	230E	4304737214	15576		1	GW	TA	SENW		1	WSMVD	TA	UTU-38419	N2995
BONANZA 1023-6P	06	100S	230E	4304737323	16794		1	GW	P	SESE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6H	06	100S	230E	4304737324	16798		1	GW	S	SENE		1	WSMVD	S	UTU-33433	N2995
BONANZA 1023-6D	06	100S	230E	4304737429	17020		1	GW	P	NWNW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6B	06	100S	230E	4304740398	18291		1	GW	P	NWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-6M1BS	06	100S	230E	4304750452	17578		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N1AS	06	100S	230E	4304750453	17581		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N1CS	06	100S	230E	4304750454	17580		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N4BS	06	100S	230E	4304750455	17579		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6I2S	06	100S	230E	4304750457	17790		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6I4S	06	100S	230E	4304750458	17792		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6J3S	06	100S	230E	4304750459	17791		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6P1S	06	100S	230E	4304750460	17793		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6A2CS	06	100S	230E	4304751430	18292		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6B4BS	06	100S	230E	4304751431	18293		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6B4CS	06	100S	230E	4304751432	18294		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6C4BS	06	100S	230E	4304751449	18318		1	GW	P	NENW	D	1	WSMVD	P	UTU38419	N2995
BONANZA 1023-6D1DS	06	100S	230E	4304751451	18316		1	GW	P	NENW	D	1	WSMVD	P	UTU38419	N2995
FLAT MESA FEDERAL 2-7	07	100S	230E	4304730545	18244		1	GW	S	NENW		1	WSMVD	S	U-38420	N2995
BONANZA 1023-7B	07	100S	230E	4304735172	13943		1	GW	P	NWNE		1	MVRD	P	U-38420	N2995
BONANZA 1023-7L	07	100S	230E	4304735289	14054		1	GW	P	NWSW		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7D	07	100S	230E	4304735393	14171		1	GW	P	NWNW		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7P	07	100S	230E	4304735510	14296		1	GW	P	SESE		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7H	07	100S	230E	4304736742	15921		1	GW	P	SENE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7NX (RIGSKID)	07	100S	230E	4304736932	15923		1	GW	P	SESW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7M	07	100S	230E	4304737215	16715		1	GW	P	SWSW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7K	07	100S	230E	4304737216	16714		1	GW	P	NESW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7E	07	100S	230E	4304737217	16870		1	GW	P	SWNW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7G	07	100S	230E	4304737326	16765		1	GW	P	SWNE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7A	07	100S	230E	4304737327	16796		1	GW	P	NENE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7O	07	100S	230E	4304738304	16713		1	GW	P	SWSE		1	MVRD	P	UTU-38420	N2995
BONANZA 1023-7B-3	07	100S	230E	4304738912	17016		1	GW	P	NWNE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-07JT	07	100S	230E	4304739390	16869		1	GW	P	NWSE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7J2AS	07	100S	230E	4304750474	17494		1	GW	P	NWSE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7J2DS	07	100S	230E	4304750475	17495		1	GW	P	NWSE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7L3DS	07	100S	230E	4304750476	17939		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7M2AS	07	100S	230E	4304750477	17942		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7N2AS	07	100S	230E	4304750478	17940		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7N2DS	07	100S	230E	4304750479	17941		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7O4S	07	100S	230E	4304750480	17918		1	GW	P	SESE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7P2S	07	100S	230E	4304750482	17919		1	GW	P	SESE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 8-2	08	100S	230E	4304734087	13851		1	GW	P	SESE		1	MVRD	P	U-37355	N2995

BONANZA 8-3	08	100S	230E	4304734770	13843	1	GW	P	NWNW		1	MVRD	P	U-37355	N2995
BONANZA 1023-8A	08	100S	230E	4304735718	14932	1	GW	P	NENE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8L	08	100S	230E	4304735719	14876	1	GW	P	NWSW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8N	08	100S	230E	4304735720	15104	1	GW	P	SESW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8F	08	100S	230E	4304735989	14877	1	GW	S	SENW		1	WSMVD	S	UTU-37355	N2995
BONANZA 1023-8I	08	100S	230E	4304738215	16358	1	GW	P	NESE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8K	08	100S	230E	4304738216	16354	1	GW	P	NESW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8M	08	100S	230E	4304738217	16564	1	GW	P	SWSW		1	MVRD	P	UTU-37355	N2995
BONANZA 1023-8G	08	100S	230E	4304738218	16903	1	GW	P	SWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8E	08	100S	230E	4304738219	16397	1	GW	P	SWNW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8C	08	100S	230E	4304738220	16355	1	GW	P	NENW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8B	08	100S	230E	4304738221	16292	1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8H	08	100S	230E	4304738222	16353	1	GW	P	SENE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8O	08	100S	230E	4304738305	16392	1	GW	P	SWSE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8B-4	08	100S	230E	4304738914	17019	1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8A1DS	08	100S	230E	4304750481	17518	1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8A4BS	08	100S	230E	4304750483	17519	1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B1AS	08	100S	230E	4304750484	17520	1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B2AS	08	100S	230E	4304750485	17521	1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O2S	08	100S	230E	4304750495	17511	1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J1S	08	100S	230E	4304750496	17509	1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O3S	08	100S	230E	4304750497	17512	1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J3	08	100S	230E	4304750498	17510	1	GW	P	NWSE		1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8C4CS	08	100S	230E	4304750499	17544	1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8D2DS	08	100S	230E	4304750500	17546	1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8D3DS	08	100S	230E	4304750501	17545	1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F3DS	08	100S	230E	4304750502	17543	1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8A4CS	08	100S	230E	4304751131	18169	1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B3BS	08	100S	230E	4304751132	18167	1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8C1AS	08	100S	230E	4304751133	18166	1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8G3AS	08	100S	230E	4304751134	18168	1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8E2AS	08	100S	230E	4304751135	18227	1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F3BS	08	100S	230E	4304751136	18227	1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F4AS	08	100S	230E	4304751137	18224	1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F4DS	08	100S	230E	4304751138	18225	1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J2CS	08	100S	230E	4304751139	18226	1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8G4DS	08	100S	230E	4304751140	18144	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H2DS	08	100S	230E	4304751141	18142	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H3DS	08	100S	230E	4304751142	18143	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H4DS	08	100S	230E	4304751143	18141	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8I4BS	08	100S	230E	4304751144	18155	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J4BS	08	100S	230E	4304751145	18154	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P1AS	08	100S	230E	4304751146	18156	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P2BS	08	100S	230E	4304751147	18153	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P4AS	08	100S	230E	4304751148	18157	1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8E2DS	08	100S	230E	4304751149	18201	1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995

BONANZA 1023-8E3DS	08	100S	230E	4304751150	18200		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8K1CS	08	100S	230E	4304751151	18199		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8K4CS	08	100S	230E	4304751152	18198		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8L3DS	08	100S	230E	4304751153	18197		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8M2AS	08	100S	230E	4304751154	18217		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8M2DS	08	100S	230E	4304751155	18216		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8N2BS	08	100S	230E	4304751156	18218		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O3CS	08	100S	230E	4304751157	18254		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8N3DS	08	100S	230E	4304751158	18215		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O4AS	08	100S	230E	4304751159	18252		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P2CS	08	100S	230E	4304751160	18251		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P3CS	08	100S	230E	4304751161	18253		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
CANYON FEDERAL 2-9	09	100S	230E	4304731504	1468		1	GW	P	NENW		1	MVRD	P	U-37355	N2995
SOUTHMAN CANYON 9-3-M	09	100S	230E	4304732540	11767		1	GW	S	SWSW		1	MVRD	S	UTU-37355	N2995
SOUTHMAN CANYON 9-4-J	09	100S	230E	4304732541	11685		1	GW	S	NWSE		1	MVRD	S	UTU-37355	N2995
BONANZA 9-6	09	100S	230E	4304734771	13852		1	GW	P	NWNE		1	MVRD	P	U-37355	N2995
BONANZA 9-5	09	100S	230E	4304734866	13892		1	GW	P	SESW		1	MVRD	P	U-37355	N2995
BONANZA 1023-9E	09	100S	230E	4304735620	14931		1	GW	P	SWNW		1	WSMVD	P	U-37355	N2995
BONANZA 1023-9I	09	100S	230E	4304738223	16766		1	GW	P	NESE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9D	09	100S	230E	4304738306	16398		1	GW	P	NWNW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9J	09	100S	230E	4304738811	16989		1	GW	P	NWSE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9B3BS	09	100S	230E	4304750503	17965		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9B3CS	09	100S	230E	4304750504	17968		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9H2BS	09	100S	230E	4304750505	17966		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9H2CS	09	100S	230E	4304750506	17967		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 10-2	10	100S	230E	4304734704	13782		1	GW	P	NWNW		1	MVRD	P	U-72028	N2995
BONANZA 1023-10L	10	100S	230E	4304735660	15164		1	GW	P	NWSW		1	WSMVD	P	U-38261	N2995
BONANZA 1023-10E	10	100S	230E	4304738224	16501		1	GW	P	SWNW		1	MVRD	P	UTU-72028	N2995
BONANZA 1023-10C	10	100S	230E	4304738228	16500		1	GW	P	NENW		1	MVRD	P	UTU-72028	N2995
BONANZA 1023-10C-4	10	100S	230E	4304738915	17015		1	GW	P	NENW		1	MVRD	P	UTU-72028	N2995
BONANZA 11-2 ✯	11	100S	230E	4304734773	13768		1	GW	P	SWNW		1	MVMCS	P	UTU-38425	N2995
BONANZA 1023-11K	11	100S	230E	4304735631	15132		1	GW	P	NESW		1	WSMVD	P	UTU-38425	N2995
BONANZA 1023-11B	11	100S	230E	4304738230	16764		1	GW	P	NWNE		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11F	11	100S	230E	4304738232	16797		1	GW	P	SENW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11D	11	100S	230E	4304738233	16711		1	GW	P	NWNW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11G	11	100S	230E	4304738235	16826		1	GW	P	SWNE		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11C	11	100S	230E	4304738309	16736		1	GW	P	NENW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11J	11	100S	230E	4304738310	16839		1	GW	P	NWSE		1	WSMVD	P	UTU-38424	N2995
BONANZA 1023-11N	11	100S	230E	4304738311	16646		1	GW	P	SESW		1	MVRD	P	UTU-38424	N2995
BONANZA 1023-11M	11	100S	230E	4304738312	16687		1	GW	P	SWSW		1	MVRD	P	UTU-38424	N2995
BONANZA 1023-11L	11	100S	230E	4304738812	16987		1	GW	P	NWSW		1	WSMVD	P	UTU-38424	N2995
NSO FEDERAL 1-12	12	100S	230E	4304730560	1480		1	GW	P	NENW		1	MVRD	P	UTU-38423	N2995
WHITE RIVER 1-14	14	100S	230E	4304730481	1500		1	GW	S	NENW		1	MVRD	S	U-38427	N2995
BONANZA 1023-14D	14	100S	230E	4304737030	16799		1	GW	P	NWNW		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-14C	14	100S	230E	4304738299	16623		1	GW	P	NENW		1	MVRD	P	UTU-38427	N2995
BONANZA FEDERAL 3-15	15	100S	230E	4304731278	8406		1	GW	P	NENW		1	MVRD	P	U-38428	N2995

✯ not moved into unit

BONANZA 1023-15H	15	100S	230E	4304738316	16688	1	GW	P	SENE		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-15J	15	100S	230E	4304738817	16988	1	GW	P	NWSE		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-15H4CS	15	100S	230E	4304750741	17492	1	GW	P	NESE	D	1	MVRD	P	UTU 38427	N2995
BONANZA 1023-15I2AS	15	100S	230E	4304750742	17493	1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
BONANZA 1023-15I4BS	15	100S	230E	4304750743	17490	1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
BONANZA 1023-15P1BS	15	100S	230E	4304750744	17491	1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
LOOKOUT POINT STATE 1-16	16	100S	230E	4304730544	1495	3	GW	P	NESE		3	WSMVD	P	ML-22186-A	N2995
BONANZA 1023-16J	16	100S	230E	4304737092	15987	3	GW	OPS	NWSE		3	WSMVD	OPS	ML-22186-A	N2995
BONANZA 1023-17B	17	100S	230E	4304735747	15165	1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-17C	17	100S	230E	4304738237	16585	1	GW	P	NENW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-17D3S	17	100S	230E	4304750511	17943	1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E2S	17	100S	230E	4304750512	17944	1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E3AS	17	100S	230E	4304750513	17945	1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E3CS	17	100S	230E	4304750514	17946	1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-18G	18	100S	230E	4304735621	14410	1	GW	P	SWNE		1	WSMVD	P	U-38241	N2995
BONANZA 1023-18B	18	100S	230E	4304735721	14395	1	GW	P	NWNE		1	WSMVD	P	U-38421	N2995
BONANZA 1023-18DX (RIGSKID)	18	100S	230E	4304736218	14668	1	GW	P	NWNW		1	WSMVD	P	U-38241	N2995
BONANZA 1023-18A	18	100S	230E	4304738243	16625	1	GW	P	NENE		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18F	18	100S	230E	4304738244	16624	1	GW	P	SENW		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18E	18	100S	230E	4304738245	16645	1	GW	P	SWNW		1	MVRD	P	UTU-38421	N2995
BONANZA 1023-18C	18	100S	230E	4304738246	16734	1	GW	P	NENW		1	MVRD	P	UTU-38421	N2995
BONANZA 1023-18G-1	18	100S	230E	4304738916	17135	1	GW	P	SWNE		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18D3AS	18	100S	230E	4304750448	17498	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18D3DS	18	100S	230E	4304750449	17499	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18E2DS	18	100S	230E	4304750450	17497	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18E3AS	18	100S	230E	4304750451	17496	1	GW	P	SENW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18L2S	18	100S	230E	4304750520	18111	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18L3S	18	100S	230E	4304750521	18110	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18K3AS	18	100S	230E	4304751061	18112	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18K3BS	18	100S	230E	4304751063	18113	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18M2AS	18	100S	230E	4304751064	18117	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18M2DS	18	100S	230E	4304751065	18116	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18N2AS	18	100S	230E	4304751066	18114	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18N2DS	18	100S	230E	4304751067	18115	1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-10F	10	100S	230E	4304738225	16565		GW	P	SENW			MVRD	P	UTU 72028	N2995
BONANZA 1023-6D1AS	6	100S	230E	4304751450	18320		GW	P	NENW	D		WSMVD	P	UTU 38419	N2995
BONANZA 1023-6C1CS	6	100S	230E	4304751448	18319		GW		NENW	D				UTU 38419	N2995
BONANZA 1023-6D3AS	6	100S	230E	4304751452	18317		GW	P	NENW	D		WSMVD	P	UTU 38419	N2995